



**Finance**  
Purchasing Division  
305 Chestnut Street  
Post Office Box 1810  
Wilmington, NC 28402-1810



910 341-7830  
910 341-7842 fax  
wilmingtonnc.gov  
Dial 711 TTY/Voice

**ADDENDUM NUMBER 1  
CITY OF WILMINGTON  
ACTION PRINTING AND GRAPHICS PARKING LOT  
PAV-IH-1111  
JANUARY 19, 2012**

To all holders of contract documents:

1. Changes in the Proposal: The previous proposal shall be discarded and replaced with the attached proposal dated January 18, 2012. **USE THIS REVISED PROPOSAL TO SUBMITT YOUR BID.**

A. Item 26 – 6’ Treated Wood Screen Fence at Dumpster Pad is changed to read: “8’ Treated Wood Screen Fence at dumpster Pad per Plan Sht. #8 and Paragraph T-15.42, complete-in-place”

B. Item 28 – 6” PVC Roof Drain bid item is added to the proposal.

C. Item 29 – 4” Steel Bollard bid item is added to the proposal.

2. Changes to the Plans:

A. Sheet 8: Clarification to the 8’ Buffer Fence Detail – The 1”X 6” Vertical Fencing is to be placed on an alternate pattern on each side.

B. Sheet 8: The Dumpster Fence Detail is revised to be 8’ high with the same section as the Buffer Fence, with the exception that the 1”x 6” vertical fencing shall be installed on the outside of the fence.

**All other terms and conditions remain unchanged.  
Daryle L.Parker, Purchasing Manager  
Purchasing Division  
END OF ADDENDUM ONE**

**PROPOSAL FOR REPLACEMENT PARKING  
FOR ACTION PRINTING - 4852 RANDALL PARKWAY**

Jan-12

| ITEM # | DESCRIPTION   | ESTIMATED QUANTITY | UNIT | UNIT COST | TOTAL COST |
|--------|---|--------------------|------|-----------|------------|
| 1      | Mobilization per Section T-15.04  | 1                  | LS   | \$        | \$         |
| 2      | Erosion Control, complete in place, per Section T-13, paragraph T-15.05 and City Standard Details SD 15.09 & SD 13.02               | 1                  | LS   | \$        | \$         |
| 3      | Clearing and Grubbing per Section T-1 and paragraph T-15.26   | 500                | SY   | \$        | \$         |
| 4      | Remove existing trees, 6-in. dia. or greater, per paragraph T-15.27 and project plans   | 11                 | EA   | \$        | \$         |
| 5      | Demolition and removal of existing pavement per Paragraphs T-15.02 & T-15.37.2  | 350                | SY   | \$        | \$         |
| 6      | Demolition and removal of existing curbing per Paragraphs T-15.02 & T-15.37.1   | 120                | LF   | \$        | \$         |
| 7      | Demolition and removal of existing gravel driveway per ST-15.02 & T-15.37   | 235                | SY   | \$        | \$         |
| 8      | Unclassified excavation, per Section T-1 and paragraphs T-15.30, T-15.31, & T-15.32   | 100                | CY   | \$        | \$         |
| 9      | Drainage Ditch excavation per Sections T-1, & T-15.30   | 35                 | LF   | \$        | \$         |
| 10     | Install 2-in. asphalt concrete surface course, Type S 9.5B, per Section T-9, complete in place                                      | 370                | SY   | \$        | \$         |
| 11     | Install 4-in. aggregate base course, (ABC), complete in place, per Section T-10   | 370                | SY   | \$        | \$         |
| 12     | Install vertical concrete curb, 6"X12", complete in place per Section 7 and Detail on Plan Sheet #7                                 | 195                | LF   | \$        | \$         |
| 13     | Install 6-in. thick concrete driveway complete in place per Section T-8, City Standard Detail SD 8-05, & Paragraph T-15.39          | 92                 | SY   | \$        | \$         |
| 14     | Install 4-in thick concrete sidewalk, complete-in-place per Section 7   | 10                 | SY   | \$        | \$         |
| 15     | Concrete dumpster pad, 8' X 8' X 6" thick, w/ 6x6-W1.4xW1.4WWF, & 4 bollards, per detail Plan Sht. 8 and T-15.43, complete-in-place | 8                  | SY   | \$        | \$         |
| 16     | Install 12" RCP, Class III, complete in place, per Section T-2  | 72                 | LF   | \$        | \$         |
| 17     | 2' X 2' Drop inlet per SD 2-02 & T-15.36, complete in place   | 2                  | EA   | \$        | \$         |
| 18     | Excavate and install 4" gravel drive 10' wide to existing house at 4830 Randall Parkway per Plan Sheet No. 2 and T-15.2             | 215                | LF   | \$        | \$         |
| 19     | Topsoil for landscape areas, per paragraph T-16.07.1, complete in place   | 400                | SY   | \$        | \$         |
| 20     | Permanent seeding of disturbed areas, complete in place per Sections T-13, and T-16   | 1,100              | SY   | \$        | \$         |

|              |  |       |    |    |    |
|--------------|--|-------|----|----|----|
| 21           | Mulching of disturbed areas, complete in place per Sections T-13 & T-16  | 1,100 | SY | \$ | \$ |
| 22           | White paint striping for parking stalls-4" wide, per Section 11  | 126   | LF | \$ | \$ |
| 23           | White paint-handicapped symbol per Section 11  | 1     | EA | \$ | \$ |
| 24           | Landscaping, complete-in-place per Section T-16 and Plan Sht. # 6  | 1     | LS | \$ | \$ |
| 25           | 8' Treated Wood Buffer Fence per Plan Sht. #8 and Paragraph T-15.42, complete-in-place   | 196   | LF | \$ | \$ |
| 26           | 8' Treated Wood Screen Fence at Dumpster Pad per Plan Sht.#8 and Paragraph T-15.42, complete-in-place  | 30    | LF | \$ | \$ |
| 27           | Install handicapped parking sign, "R7-8E" with van accessible signage and "U" galvanized channel post. Attach to post with 5/16" dia. Hex head galvanized bolts w/face washer and lockwasher | 1     | EA | \$ | \$ |
| 28           | Install 6" PVC Roof Drain, per Plan Sht. #4 and Paragraph T-2.06 including clean-out and fittings  | 140   | LF | \$ | \$ |
| 29           | Install 4' steel bollards as detailed on Plan Sht #8 and shown on Plan Sht# 3 at the transformer and air conditioning units  | 6     | EA | \$ | \$ |
| <b>TOTAL</b> |  |       |    |    | \$ |